625

MYSORE RAILWAYS.

Notification dated 15th October 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Railways, Hassan, up to 15th November 1927, for constructing one block of two units for two Augwallas at Tarikere. An approximate estimate of quantities is given in the following schedule. The quantities are not guaranteed. The work should be completed by the end of March 1928 showing continuous equal monthly progress.

2. Plans, detailed estimate and conditions of schedule agreement, may be seen at the Executive Engineer's Office at Mysore Railways, Hassan, on all working days between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of one rupee.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and should be superscribed "Tenders for constructing one block of two units for Augwallas at Tarikere", in default of which, tenders will be rejected.

5. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned early.

6. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. The name of the competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement, in default of which, his tender will be considered cancelled.

SCHEDULE.

No.	Items of work	Unit	Quantity	Rate
1	Earthwork excavation including filling in basement	1,000 C.ft.	722	
2	Concrete broken stone in mortar	100 C.ft.	255	
3	Burnt brick in mortar	100 C.ft.	601	
4	Burnt stone slabs 6" dressed	Sq.ft.	75	
5	Plastering with mortar	100 S.ft.	2,300	
6	White and color washing	,,	2,300	
7	Battened door with teak wood frame and jungle wood shutters including fittings, etc., complete, as per design.	Sq.ft.	66	
8	Jungle wood windows and ventilators battened with frames and fittings, Iron bars $\frac{3}{4}$" square fixed at 4" centres with fittings, etc., complete as per design.	Sq.ft.	16	
9	Teak wood wrought and put up including wood oiling.	Cubic ft.	26·91	
10	Roofing with 1st class Mangalore tiles over teak reepers including chunam borders, wind ties, etc., complete.	100 S.ft.	633	
11	Mangalore ridge tiles set in mortar	R.ft.	27	
12	Painting with silicate chocolate paint	100 S.ft.	130	
13	Flooring with gravel 6" thick wellrammed	,,	275	
14	Providing sinks 2' x 2' withc Cuddapah slab flooring	Each	2	
15	Providing teak wood planks for shelves (1" thick)	S.ft.	5	
16	Providing masonry drains 6" x 6" over 1 ft. concrete and $4\frac{1}{2}$" side walls brick in mortar and cement plastered $\frac{1}{2}$" thick.	R.ft.	80	
17	Flooring with Cuddapah slabs 2" thick over a bed of 3" concrete and cement pointed.	100 S.ft.	300	
18	Burnt brick in mud	100 C.ft.	794	

V. RAMANJULU NAIDU,
Executive Engineer.